

CT Enclosure

- Type 3R, ANSI 61 gray
- Removable hinged or non-hinged door(s) w/ sealing and locking provisions
- Service Ampacity: 201-800 amps
- Cabinet WxHxD: 36x36x11 (min)

CT Landing Platforms


Part #'s or Equivalent

- For bar type ANSI C12.11 CT's
- 600V, 50kA AIC
- Line & Load side Mechanical Lugs

Cooper B-Line	Milbank
6067 HEEL	K4722

Notes:

- 1) The customer supplies and installs the current transformer enclosure, CT landing platform. IPL supplies and the customer installs the meter base. IPL supplies and installs the current transformer, instrument wiring and meter.
- 2) IPL will supply, install and connect conductor to the line side only on UNDERGROUND services. The customer supplies, installs and connects conductor on OVERHEAD services.
- 3) Hi leg/wild leg on 3 phase 4 wire delta services must be on the right hand side of the CT landing platform.
- 4) 3 Phase meter base, test block and metering supplies will be paid for by the member but, supplied by IPL and delivered to contractor to install with CT Enclosure.

ENGINEER:		3 PHASE CT METERING 201-800 AMP SERVICE				 INLAND POWER AND LIGHT CO.			
REVISED	IPL APR-13								PERM 3P-201-800