



NOTE:

THE TEMPORARY SERVICE MUST BE WITHIN 5 FEET OF THE UTILITY'S HANDHOLE, SECONDARY STUBOUT OR TRANSFORMER. LOCATION OF TEMPORARY SERVICES BEYOND 5' MUST BE APPROVED BY THE UTILITY.

ITEMS OWNED AND INSTALLED BY THE MEMBER:

1. 6"x 6"x 8' MINIMUM CONTINUOUS SINGLE STRUCTURE
2. 2" x 4" BRACING (POST SHOULD BE BRACED IN TWO DIRECTIONS)
3. METER SOCKET AND DISTRIBUTION PANEL (100-200AMP, 120 /240 VOLT)
4. GROUND WIRE IN ACCORDANCE WITH NEC
5. GROUND RODS IN ACCORDANCE WITH NEC
6. SERVICE ENTRANCE CONDUCTORS IN ACCORDANCE WITH NEC

ITEMS OWNED AND INSTALLED BY THE UTILITY:

7. TRANSFORMER, HANDHOLE OR STUBOUT
8. METER

ITEM	MATERIAL	ITEM	MATERIAL
ENGINEER:		INLAND POWER AND LIGHT CO.	
NEW CONSTRUCTION SPECIFICATIONS TEMPORARY UNDERGROUND SERVICE		TEMP UG	
REVISED	IPL OCT-10		